

**Title**: PMT / HIgh Speed Camera Stage **Contact**: David Mittelstein (dmittels@caltech.edu)

**Date:** Dec 4, 2018

## **Job Notes**

Finished wood (minimal exposed wood b/c working with optics) 3/4" thick, all THRU ALL holes must be through entire material Will be used as a shelf to support ~100 lb of equipment 48 clearance screw holes for 1/4" screws 24 counterbore clearance screw holes for 5/16" hex screws \* Important that counterbore is complete and screws are not sticking out